SURFSIDE PAINTING COMPANY

PROPOSAL

November 9, 2026

PREPARED BY

Jon Long
2110 N Ventura Ave
Ventura, CA 93001
805-798-4995
jon@surfsidepaint.com

PREPARED FOR

Divine Builders
Brian Briggs
819 Loma Dr
Ojai, CA 93023
805-798-2830
divinebuilder1@gmail.com

PROJECT SUMMARY

This project involves the completion of exterior repairs, surface preparation, priming, and painting as part of the ongoing renovation at **1693 Poli Street, Ventura, CA**. All work to be completed at a professional contractor-grade finish with an emphasis on expedited scheduling and rapid completion.

SCOPE OF WORK

Pressure wash designated exterior areas and allow surfaces to dry. Prioritize repair of the fascia where the 8-inch piece was removed, then prepare, prime, and paint the red fascia throughout so gutter installation can proceed. Fill holes and patch damaged stucco in affected areas, including the retaining wall; apply stucco above the detached structure entrance; and patch and finish the area near the utility lines. Fill pest-damaged areas beneath the eaves as needed and address the vent penetration beneath the eaves. Caulk under-eave joints as needed and seal extensive stucco cracks, including cracks at inside corners, with elastomeric caulking. Complete remaining surface preparation, spot-prime repairs and other prepared areas with appropriate primers, and apply two coats of contractor-grade paint to the entire exterior. Within the detached rear structure, prime and paint newly installed drywall and finish the interior window sills.

PRICING

- **Fixed price** **$15,000.00**
  Price includes all labor. Materials are billed separately. Estimated completion time is 5-10 working days, weather permitting. Repairs are not warranted due to unforeseen substrate conditions.

- **Materials**
  Divine Builders to provide all interior and exterior paint. Additional materials will be purchased and delivered by Surfside Painting Company, invoiced at cost with a 3% delivery charge.

TERMS

Proposal is good for 30 days from the proposal date. Work is not warrantied due to unforeseen substrate conditions. Nonwaivable legal rights and obligations remain in effect. Additional work outside the scope requires a written change order, signed by both parties with price and schedule adjustments, before proceeding. Start date and payment schedule will be agreed in writing before work begins. Schedule depends on weather, drying and curing, material availability, access, and other trades. Divine Builders will confirm colors and finishes and provide access, water, power, and paint. Work areas will be protected and job-related debris removed upon completion.