SURFSIDE PAINTING COMPANY

PROPOSAL

November 9, 2026

PREPARED BY

Jon Long
2110 N Ventura Ave
Ventura, CA 93001
805-798-4995
jon@surfsidepaint.com

PREPARED FOR

Divine Builders
Brian Briggs
819 Loma Dr
Ojai, CA 93023
805-798-2830
divinebuilder1@gmail.com

PROJECT SUMMARY

Restore water damaged ceiling in hallway and install baseboard/shoe at the undisclosed project location in **Echo Park**.

SCOPE OF WORK

Protect work area with Ram Board or equivalent and 4 mil wall plastic. Install R13 insulation. Install 5/8-inch Type X drywall in the 8.5-foot by 12-foot ceiling area and new drywall in the 16-inch by 4.5-foot skylight area. Install corner bead on outside corners around skylight. Tape drywall seams and inside corners, float into existing drywall, and finish to Level 3. Prime, texture to match and paint two coats of interior paint. Install baseboard and base shoe.

PRICING

- **Fixed price** **$5,000.00**
  Includes all labor and supplied materials. Estimated completion: 3-5 working days. Surfside requests the use of an industrial dehumidifier to accelerate drying.

- **Materials**
  Divine Builders provides all required materials, including drywall, drywall tape, taping compound, topping, baseboard, base shoe, PVA primer, paint and protection materials. Materials not provided will be purchased and delivered by Surfside Painting Company, invoiced at cost with a 3% delivery charge.

TERMS

Proposal is valid for 30 days from the proposal date. No voluntary warranty is offered for this restoration work because additional water leaks may exist. Nonwaivable rights and obligations remain unaffected. Extra work requires a written change order, signed by both parties with price and schedule adjustments, before proceeding. Start date and payment schedule will be agreed in writing before work begins. Timing depends on drying, material availability, access, and other trades. Work areas will be protected and job-related debris removed upon completion.